BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Improvents to Roads and Drains at Ambedkarnagar, LBS nagara and Allalasandra in Ward No.04 at Yelahanka Newtown

Agency:- Sri. G VENKATE GOWDA

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of Sri. G VENKATE GOWDA		
			Unit	Rate in Figures	Rate in Words
1	943.20	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications,	Cum	220.60	Rupees Two Hundred Twenty And Paise Sixty Only
2	943.20	Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading.	Cum	116.73	Rupees One Hundred Sixteen And Paise Seventy Three Only
3	309.90	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5681.10	Rupees Five Thousand Six Hundred Eighty One And Paise Ten Only
4	264.00	construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller)	Cum	352.50	Rupees Three Hundred Fifty Two And Paise Fifty Only
5	198.00	Construction of granular sub-base by providing close graded material, crushed stone aggregates of granite/trap/basalt material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method.Close graded granular sub-base material as per 400-1 For Grading- II Material	Cum	1833.78	Rupees One Thousand Eight Hundred Thirty Three And Paise Seventy Eight Only
6	220.11	Providing laying plain/ reinforced cement concrete M20 Grade for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc. complete as per approved drawing and design	Cum	12149.00	Rupees Twelve Thousand One Hundred Forty Nine Only
7	143.07	providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.	MT	7097.80	Rupees Seven Thousand Ninety Seven And Paise Eighty Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

18/2/19

	App Qty	Description of work	Approved Rates of Sri. G VENKATE GOWDA		
			Unit	Rate in Figures	Rate in Words
8	455.40	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge.	Sqm	2312.52	Rupees Two Thousand Three Hundred Twelve And Paise Fifty Two Only
9	397.62	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc.,	Cum	6862.40	Rupees Six Thousand Eight Hundred Sixty Two And Paise Forty Only
10	2499.00	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift.	Sqm	105.00	Rupees One Hundred Five Only
11	795.00	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement	Rmt	134.25	Rupees One Hundred Thirty Four And Paise Twenty Five Only
12	1149.44	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.	No	424.90	Rupees Four Hundred Twenty Four And Paise
13	346.40	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	30.34	Rupees Thirty And Paise Thirty Four Only
14	346.40	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	77.00	Rupees Seventy Seven Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

18/2
19